



**KENYA ELECTRICITY TRANSMISSION CO.**

Kawi Complex, Block B,  
Popo Lane, Off Red Cross Road, South C  
P. O. Box 34942 – 00100, NAIROBI  
Phone: 020 4956000, 0719018000, 0732128000  
Web: [www.ketraco.co.ke](http://www.ketraco.co.ke) • email: [info@ketraco.co.ke](mailto:info@ketraco.co.ke)

**Our Ref: KETRACO/PT/014/2023**

**10<sup>th</sup> May,2023**

**Notice to all Bidders.**

**RE: TENDER ADDENDUM AND CLARIFICATION 2**

**RE: TENDER FOR PROCUREMENT OF TRANSMISSION LINE INSULATORS FOR OVERHEAD LINES MAINTENANCE WORKS. (TENDER NO. KETRACO/PT/014/2023)**

The following amendments are made to the specified provisions of the tender for Procurement of Transmission Line Insulators for Overhead Lines Maintenance Works. **(Tender No. KETRACO/PT/014/2023).**

Find herein the Tender Addendum and Clarification No. 2, consisting of five pages. This document should be attached to the completed Form of Tender.

The Closing Date shall be **25<sup>th</sup> May 2023 at 10.00am** Local time.

**PETER NJEHIA**  
**SENIOR MANAGER, SUPPLY CHAIN**



**TENDER FOR PROCUREMENT OF TRANSMISSION LINE INSULATORS FOR OVERHEAD LINES MAINTENANCE WORKS. (TENDER NO. KETRACO/PT/014/2023) TENDER CLARIFICATION 2**

s.no	CLARIFICATION SOUGHT BY BIDDERS	KETRACO RESPONSE
1	<p>Please inform if there is requirement of turn buckle (with or without) for tension Insulator string assembly for all KV ratings as per bill of quantities (BOQ).</p> <p>Please inform the type of clamp for suspension insulator string assembly for all KV ratings as per bill of quantities (BOQ).</p> <p>As per 1.2.1.2 clause of GTP of insulator, minimum failing load is 70/100 kN for 132 kV suspension insulator string assembly whereas minimum failing load is 120 kN for 132 kV insulator unit as per 1.1.2.5 clause. Please clarify which one is correct.</p>	<p>Refer to new BOQ provided.</p> <p>Refer to the technical specifications provided</p> <p>70/100kN for Insulator string &amp; 120kN for Insulator unit (Long Rod)</p>
2	<p>Kindly assist our manufacturer in interpreting the price schedule for each insulator as the description reads "Supply of tension/suspension Insulator string assembly, complete with necessary hardware, fittings etc. for single conductor type". The manufacturer would like to know what "string assembly complete with necessary hardware and fittings" entails. What comprises the hardware and fittings requested?</p> <p>Which incoterms should we use when quoting our price?</p>	<p>Refer to new BOQ provided</p> <p>Delivered Duty Paid (DDP), KETRACO Isinya Yard</p>
3	<p>We would also like to request an extension of the tender closing date.</p> <p>According to paragraph 3.3.4, that means "2% Bid Security/tender security from a reputable financial institution (issued by Banks Licensed by the Central Bank of Kenya)" Since this company is not Kenyan, it cannot give a bank guarantee from Kenya. This company can give a bank guarantee from Emirates Bank. Is this confirmed?</p>	<p>Closing date extended to May 25<sup>th</sup>, 2023 @10.00am Local time</p> <p>Issuing Bank shall be licensed by Central Bank of Kenya</p>
4	<p>We are pleased to inform you that for getting the bid security prepared from a reputable financial institution, it will take minimum 10-15 days time. In view of above, we request you to</p>	<p>Closing date extended to May 25<sup>th</sup>, 2023 @10.00am Local time</p>



	<p>kindly extend the due date by one month, enabling us to get prepared the bid security &amp; submit our tender.</p> <p>We are still sourcing for the Insulators requested in the subject tender as they are extra high voltage insulators not easily available in the market.</p> <p>We are therefore requesting for extension of the closing date by two weeks to 25th May 2023</p>	<p>Closing date extended to May 25<sup>th</sup>, 2023 @ <b>10.00am</b> Local time</p>
--	--	---



**REVISED BOQ**  
**TENDER FOR SUPPLY OF TRANSMISSION LINE INSULATORS & FITTINGS: 132KV, 220KV & 400KV**  
**PRICE SCHEDULE/BILL OF QUANTITIES**

Name of tenderer \_\_\_\_\_ Tender Number \_\_\_\_\_ Page \_\_\_\_\_ of \_\_\_\_\_

1	2	3	4	5	6=4x5
Item no.	Item description	Quantity	Unit	Unit Price	Total Price
1.0	<b>132kV CONDUCTOR INSULATORS &amp; FITTINGS</b>				
	Supply of Complete Insulator Sets including insulators and all fittings between tower and Conductor (Suitable for <b>Single ACSR Lynx</b> conductor), including all types of clamps, extension links, Armor rods and all connections to Towers.				
1.01	Single Suspension String	200	Set		
1.02	Double Suspension String	-	Set		
1.03	Single Tension String	200	Set		
1.04	Double Tension String	-	Set		
2.0	<b>220kV CONDUCTOR INSULATORS &amp; FITTINGS</b>				
	Supply of Complete Insulator Sets including insulators and all fittings between tower and Conductor (suitable for <b>Single ACSR Canary</b> conductor), including all types of clamps, extension links, Armor rods, and all connections to Towers.				
2.01	Single Suspension String	200	Set		
2.02	Double Suspension String	-	Set		
2.03	Single Tension String	200	Set		
2.04	Double Tension String	-	Set		





3.0	<b>400kV CONDUCTOR INSULATORS &amp; FITTINGS</b>					
	Supply of Complete Insulator Sets including insulators and all fittings between tower and Conductor (suitable for <b>Triple ACSR Conductor</b> ), including all types of clamps, extension links, Armor rods, and all connections to Towers.					
3.01	Single Suspension String	200			Set	
3.02	Double Suspension String	-			Set	
3.03	Single Tension String	200			Set	
3.04	Double Tension String	-			Set	
4.0	<b>400kV CONDUCTOR INSULATORS &amp; FITTINGS</b>					
	Supply of Complete Insulator Sets including insulators and all fittings between tower and Conductor (suitable for <b>Quad ACSR Lark conductor</b> ), including all types of clamps, extension links, Armor rods, and all connections to Towers.					
4.01	Single Suspension String	200			Set	
4.02	Double Suspension String	-			Set	
4.03	Single Tension String	200			Set	
4.04	Double Tension String	-			Set	
5.0	Factory tests on insulators at an internationally accredited testing facility including facilitation for project Employer's personnel for FATs, including all costs -max 2 staff	Lot			1	

