

Our Ref: KETRACO-PT-004-2025

12th March, 2025

Notice to all Bidders

RE: TENDER ADDENDUM AND CLARIFICATION 2 TO TENDER NUMBER , KETRACO-PT-004-2025

The following amendments are made to the specified provisions of **TENDER FOR SUPPLY AND INSTALLATION OF MODERN STORAGE SYSTEM FOR APEX GO-DOWN FACILITY, Tender No. KETRACO-PT-004-2025**

Save where expressly amended by the terms of this clarification, the Principal Tender Document shall continue to be in full force and effect.

Find herein a ADDENDUM AND CLARIFICATION No. 2, consisting of two (3) pages into the Principal Tender Documents as attached. This document should be returned along with dully filled Form of Tender.

No	Clause	Clarification	KETRACO Response
1	Zone 3- 1.3.1 Circuit breakers and large Equipment - Heavy duty pallet racking 6096x2438x1219 (HxWxD)	"Kindly confirm can we give 6000mm high to optimize space? What is the distance between each arm?"	<ul style="list-style-type: none"> The proposed 6000mm height is acceptable as an alternative to the specified 6096mm, provided all other specifications are met, including load capacity requirements. The distance between arms should be adjustable in 76mm (3") increments to accommodate various equipment sizes. Typical spacing requirements will range from 1500mm to 3000mm depending on stored equipment.
2	Zone 4 - 1.4.1 Cable storage rack 2438x1829x1219 (HxWxD)	"Kindly confirm any specific is required? Storage required for how many cable reels? What type of material handling equipment will be used?"	<ul style="list-style-type: none"> The rack should accommodate cable reels with diameters ranging from 1000mm to 2000mm. Storage is required for approximately 25 cable reels of various sizes, with total capacity as specified in the tender documents. Material handling will primarily utilize the electric counterbalance forklift (5-ton capacity)

No	Clause	Clarification	KETRACO Response
			specified in the tender, in conjunction with manual pallet jacks.
3	Zone 4 - 1.4.2 Vertical bar rack 2438x1829x1219 (HxWxD)	"Kindly confirm that we give this in racking system itself at ground level so that space is well utilized? Or do you want it in an independent location?"	<ul style="list-style-type: none"> The vertical bar rack should be installed as an independent system dedicated to long items storage. This is to ensure proper organization and easy access to bare copper conductors and other rigid items without interfering with cable reel storage. The location should be adjacent to the cable reel storage area within Zone 4.
4	Zone 5 - 1.5.1 Transmission Line Equipment - Heavy duty shelving units 2438x1219x609	"Kindly confirm this to be place upstairs or ground floor"	<ul style="list-style-type: none"> These units should be installed on the ground floor within the lower floor godown area as specified in the zoning plan. This location ensures accessibility for heavier transmission line equipment and facilitates workflow between related storage zones.
CLOSING DATE			
		Initial Closing Date	New Closing Date
5		18 th March 2025 Time 10:00 am	25 th March 2025 Time 10:30am

Bidders are expected to fill and return this addendum 2 alongside with the form of tender.

Please note that all equipment must comply with the technical specifications provided in our tender document. Any proposed alternatives must meet or exceed these specifications. All other terms and conditions of the tender document remains the same.

USER REPRESENTATIVE:

SIGNATURE:




APPROVED BY:



SENIOR MANAGER, SUPPLY CHAIN

Tender Addendum and Clarification No. 1 of Tender No. **KETRACO/PT/004/2025** has been received and incorporated in the Tender Documents.

Name of Tenderer (*in block letters*):

Signature:

Date:

**Signed for the Tenderer by
(*Name in block letters*):**

**In the office bearer capacity
of:**
