


**ELEVATION 3**

SC. 1:100



**SECTION A-A**

SC. 1:100

**NOTE:**



- 1- THE ROOF SHALL BE COVERED WITH Min. 60 MM Thick. ROOF SANDWICH PANEL.
- 2- THE DISTANCE BETWEEN GUTTER DOWN PIPES SHOULD NOT BE MORE THAN 20M.  
+THE GUTTER AND GUTTER STRAP DETAILS SHALL BE PROVIDED BY CONTRACTOR DURING EPC DETAIL DESIGN STAGE.  
WITH THE RELEVANT CALCULATION AS PER RAINFALL LEVEL AND WATER FLOW VALUE, SUBJECT TO CLIENT/CONSULTANT APPROVAL.
- 3- +ALL EXTERNAL DOORS SHALL BE MADE OF 1.6MM MIN THICKNESS ZINC-COATED STEEL SHEET WITH A PANIC LOCK.  
+ALL DOOR SHALL BE FIRE RESISTANCE.  
+ALL WINDOWS ARE DOUBLE GLAZED WITH HEAVY DUTY ANODIZED ALUMINUM FRAMES.
- 4- ALL BUILDING SHALL BE PAINTED WITH KETRACO APPROVED COLOURS.
- 5- ALL BUILDING EXTERNAL WALL FINISHING SHALL BE CEMENT PLASTER WITH WHITE FLAT EMULSION.
- 6- ULTIMATELY, THE FINAL DOOR AND WINDOW SIZES AND DESIGN SHALL BE SUBJECT TO APPROVAL BY THE EMPLOYER'S REPRESENTATIVE.
- 7- THE ROOF VENTILATOR FANS (WIND DRIVEN CYCLONES) SHALL BE PROVIDED ONE PER SLOPE PER BAY.

**INTERIOR FINISHING SCHEDULE**

ROOM NO.	ROOM NAME	FLOOR	SKIRTING	WALL
G8	STORAGE	EPOXY PAINT ON CONC.SLAB	CERAMIC TILE (H= 100 mm)	CEMENT PLASTER WITH WHITE FLAT EMULSION PAINT

ELEVATION (3) SECTION (A-A)  
FINISHING SCHEDULE & NOTE

5

REFERENCE DRAWINGS			
Drawing No.		Title	
<input type="checkbox"/> APPROVED <input type="checkbox"/> APPROVED WITH COMMENTS <input type="checkbox"/> NOT APPROVED <input type="checkbox"/> FOR INFORMATION			
DATE: _____		SIGNATURE/STAMP: _____ PROJECT CONSULTANT	
		KENYA ELECTRICITY TRANSMISSION COMPANY LTD	
		COLENGO CONSULTING LIMITED	
PROJECT: KENYA TRANSMISSION NETWORK IMPROVEMENT PROJECT (KTRNIP).			
PROJECT DRAWING NO. _____		PROJECT NO. _____	
NAME: _____ DATE: _____		TYPICAL STORAGE WAREHOUSE ARCHITECTURAL DRAWING	
PREPARED: _____		DRAWN: _____	
CHECKED: _____		APPROVED: _____	
NO. NAME DATE		ELEVATION (3) SECTION (A-A) FINISHING SCHEDULE & NOTE	
SCALE: 1:600		DWG NO. <b>SNM-FSH-001</b>	
		REV.:	